

Agency: Commerce, Community and Economic Development**Grants to Municipalities (AS 37.05.315)****Grant Recipient: Nunapitchuk****Federal Tax ID: 92-0044733****Project Title:****Project Type: Equipment and Materials**

Nunapitchuk - Eastside Cemetery

State Funding Requested: \$70,000**House District: 36 / R**

Future Funding May Be Requested

Brief Project Description:

To build a boatdock and boardwalks leading up to the new eastside cemetery.

Funding Plan:

Total Project Cost: \$70,000

Funding Already Secured: (\$0)

FY2015 State Funding Request: (\$70,000)

Project Deficit: \$0

*Funding Details:**City of Nunapitchuk has received funding from FEMA to build 24 boatdocks within the vicinity of Nunapitchuk but the new cemetery site was not included as one of the 24 boatdocks that needed repair.***Detailed Project Description and Justification:**

Nunapitchuk resides on top of marshland and clay so the land is hard to walk on with tennis shoes or normal day to day office work shoes. There are mounds of tundra land around dangerous mossy land. In order to reach the new east side cemetery we need to build a boat dock with a 500 foot boardwalk about half a mile up from the river. This boat dock is subject to be 20 ft in length x 4 ft in width with 5 (2 ft x 4 ft x 20 in) poly floats attached to the underside of the framing structure, each structure is held in place with four 4-inch galvanized steel poles. Additionally, ramp extends from the shoreline to the dock attached in a manner to allow for river tidal ebb and flow. Two duck bill anchors will be in place to hold the dock from floating away. Eight inside corners and eight outside steel corners will be attached to the floats and frame of the dock. Outside corner and side bumpers will be attached to the dock as well. Ten 2x6x10' treated lumber will be set on top of the boat dock. 5/16" x 6" lag screws will be used to screw the lumber together and nuts and bolts for the outside and inner metal corners. Three Hundred Fifty 3x10x12' treated lumber will be ordered from The Lumber Yard and shipping from Seattle to Nunapitchuk by barge will be around 15,000.00-20,000.00. One supervisor at \$25/hour will be hired to watch the whole project and six laborers at \$20/hour to help complete the project. Administrative work will also be included.

Project Timeline:

Project time line estimated two years 2015-2017 and expenditures will occur as soon as we get funded.

Entity Responsible for the Ongoing Operation and Maintenance of this Project:

No one.

Grant Recipient Contact Information:

Name:	Juliana Wassillie
Title:	City Clerk
Address:	103 Johnson Loop Nunapitchuk, Alaska 99641
Phone Number:	(907)527-5327
Email:	cityofnunap@yahoo.com

Has this project been through a public review process at the local level and is it a community priority? Yes No