

Allakaket: Airport Improvements**FY2010 Request: \$260,000**
Reference No: 40278**AP/AL:** Allocation**Project Type:** Construction**Category:** Transportation**Location:** Allakaket**Contact:** Christine Klein**House District:** Interior Villages (HD 6)**Contact Phone:** (907)269-0724**Estimated Project Dates:** 07/01/2009 - 06/30/2014**Appropriation:** Airport Improvement Program**Brief Summary and Statement of Need:**

Repair and stabilize the runway embankment, taxiway and apron to correct areas that have experienced serious differential settlement, side slope failures and erosion. Work will include resurfacing, addition of a dust palliative and lighting adjustments or replacement as needed, improve apron setback from the runway, and make other improvements as funding allows. This project contributes to the Department's Mission by reducing injuries, fatalities and property damage and by improving the mobility of people and goods.

Funding:	FY2010	FY2011	FY2012	FY2013	FY2014	FY2015	Total
Fed Rcpts	\$260,000						\$260,000
Total:	\$260,000	\$0	\$0	\$0	\$0	\$0	\$260,000

<input checked="" type="checkbox"/> State Match Required	<input type="checkbox"/> One-Time Project	<input type="checkbox"/> Phased - new	<input checked="" type="checkbox"/> Phased - underway	<input type="checkbox"/> On-Going
5% = Minimum State Match % Required		<input type="checkbox"/> Amendment	<input type="checkbox"/> Mental Health Bill	

Operating & Maintenance Costs:

	<u>Amount</u>	<u>Staff</u>
Project Development:	0	0
Ongoing Operating:	0	0
One-Time Startup:	0	0
Totals:	0	0

Additional Information / Prior Funding History:

FY2009 - \$1,950,000; FY2008 - \$400,000; FY2006 - \$4,220,000.

Project Description/Justification:

The Allakaket runway was constructed in 1997. However, the existing foundations included extensive permafrost and wet areas. Thaw-settlement has caused serious safety concerns due to differential settlement of the runway, embankment cracking along the fill slopes and safety areas, slope erosion, drainage problems and distress to the lighting system.

Additional funding needed to fund project to current cost estimate.