

**Alaska Marine Highway System - Gustavus Ferry Terminal
Modifications**

**FY2016 Request: \$3,500,000
Reference No: 60527**

- Remove two timber log floats in the harbor; relocate one to end of existing float structure (install three 12 ¾" steel piles)
- Install a new access float (assembled from a portion the existing bridge float) and steel six-pile (30") float restraint structure and, when funds become available, reinstall the steel mooring float with up to 10 three-pile restraint structures, each consisting of one 30" pile and two 18" piles
- Provide access gangways and landing platforms for lift towers, and access catwalk to existing breasting dolphins